
THE ZEST HIVE FOR B.S. NATIONAL CONVERSION OPTION 1 TO DEPLOY 600 LONG BLOCKS

ROOF

1800 X 1000 METAL SHEET HELD DOWN WITH ROPES AT EACH END ONTO ROOF BLOCKS. PROVIDE 2 SHORT PIECES OF 12 DIA.







ALLOW IN-HIVE FEEDER ACCESS)

1# 1200x450x50MM, WINTER ROOF INSULATION





BLOCK EXTERNAL ENVELOPE FLOOR WALLS AND ROOF FORMED FROM 24#600X215X100 LIGHTWEIGHT INSULATING BLOCKS.



SUPPORT EXTERNAL ENVELOPE

2# 1200X100X50 TREATED SOFTWOOD BEAMS, INSTAL OVERHANGING POLYTHENE D.P.C. (TO DETER CLIMBING VERMIN) ON 4# 440X215X100 HEAVY CONCRETE BLOCKS CANTIVERED OUT OVER EDGES OF 600X600 CONCRETE SLAB.

BLOCKS 5# TOTAL SLIDE BINDERS TO MAKE 10# 75 slide binders to allow adjustable **VOOD** access and ventilation. 2# 100 slide binders to join carrier frames in the middle of the sides INSULATION **PLASTIC** ASSEMBLY 125 LONG ELEVATION END ELEVATION Λ Λ 1300x500 PLASTIC COVER SHEET COLON COLONY

Guidance on building your ZEST hive

CROSS SECTION

1. Clear the ground and level it. Treat it with something unpleasant (like used engine oil) but not dangerous. To prevent burrowing rodents from undermining the foundation

4#CONCRETE SUPPORT BLOCKS

LONG SECTION

- 2. Lay the 600x600x38 foundation paving slab. Level with a spirit level. There is only one slab so that any uneven settlement can be easily dealt with by levering it up and repacking with earth to re-level it.
- 3. Lay the 4# 440x215x100 heavy foundation blocks on the slab as shown on the drawing, being corbelled out from the foundation paving slab.
- 4. Lay 2#1000x150 polythene d.p.c. vermin guards on the foundation blocks. 5. Lay 2#1200x100x50 treated softwood on blocks as floor support beams.
- 6. Lay 24#600x215x100 lightweight insulating blocks on the wood beams to form the floor, roof and walls. These blocks are to be as ultra lightweight as possible such as "Durox Aircrete". If not available other lightweight blocks may be used. The walls can also be formed from 16#440x215x100 ultra lightweight blocks instead of 12# 600x215x100.
- 7. Assemble the plastic carrier frame. Lay it on the block floor so that is central in both directions and mark the internal volume of the ZEST hive on the floor. Lay the wall
- 8. Ensure that the vertical joints are staggered in the second course to achieve bond. Blocks are laid loose.
- 9. Place the carrier frame onto the top course of wall blocks and ensure alignment.
- 10. Assemble and insert the plastic frames, partitions and queen excluders as required
- 11. Refer to the drawing "Zest Transition and Management Diagrams" for colony insertion from a traditional B.S. hive.
- 12. Deploy the 2# closing partition insulation boards on the side of the partition away from the bees
- 13. Deploy the plastic cover sheet on the frames and the edging.
- 14. The 6 roof blocks are placed on the top edge of the carrier frame or the wood containment frame, whichever is used.
- 15. Lay the 2000x1000 roof sheet on the roof blocks and roped down This can be scrap metal and is preferred.
- 16. Hold the roof sheet down with holding down ropes at each end with the rope passing under the floor beams. Protect the rope at the sheet edge contact points with plastic hose. Additional insulation is best deployed on the roof blocks in winter.
- Deploy the 10# slide binders at the entrances if the plastic carrier frame is deployed.
- 18. The ZEST plastic carrier frame can be replaced with a wood containment one. Ventilation and bee access holes of 22mm. (wine cork sized) will need to be drilled through the block approximately 75mm. down where show on the elevation. These will receive virgin cages which can be open or closed to bees and/or air as required.